

NAME OF WORK ADDITION AND ALTERATION WORKS TO BE CARRIED OUT IN EXISTING GARAGE, (to be converted to Kitchen/Wash area)ANNEX BUILDING, GST BHAVAN,  
NUNGAMBAKKAM, CHENNAI

Sl.No.	Description of work	Qty.	Rate	Unit	Amount
1	Raising the existing garage floor level up to 15 cm high with brick jelly 1:5:10 as per the site requirement	2.70cu.m		cu.m	
2	Construction of a cooking plat form with fire clay brick work up of size 6.0m x 0.9m x 0.7 m with necessary burner / fire openings etc as required	3.80cu.m		cu.m	
3	Providing half brick work with cement mortar 1:4 in the proposed kitchen /dining arae	10 sq.m		sq.m	
4	Providing brick work in cement mortar 1:6 at front side (existing opened area )	1.60 cu.m		cu.m	
5	Suplying and laying of anti skid floor tiles (300mm x 300 mm) on the raised floor /kitchen platform as required	28.0sq.m		sq.m	
6	Providing and fixing wooden door of size 900mm X 1200mm with wooden frame of size 100mm x70mm and flush door shutters of thickness 35mm including all accsories / locking arrange ment	1 No.		no	
7	Providing and fixing wooden window with frame size 100mm x70mm and glazed shutters of thickness 30m including all accsories / locking arrange ment				
	a) 900mmx 1200mm	1 nos		each	
8	plastering of brick work in cement mortar 1:5 for nwely constructed brickwork	35 sq.m		sq.m	

NAME OF WORK: ADDITION AND ALTERATION WORKS TO BE CARRIED OUT IN EXISTING GARAGE (to be converted to Stall / Dining area) ANNEX BUILDING, GST BHAVAN,  
NUNGAMBAKKAM, CHENNAI

Sl.no	Description of work	Qty.	Rate	Unit	Amount
1	Dismantling and removing of existing MS rolling shutters and handing over the same to the Department.	3Nos.		each	
2	Demolishing the rear side wall connecting the three garage, and disposing all the rubbish complete as etc.,	6.50 cum		cu.m	
3	Making a opening of size 900mm x 600mm in the existing partition wall of the garage, including plastering, making good the surface and disposing all the rubbish, complete as required.	1no.		no	
4	Raising the existing garage floor level up to 15 cm high with brick jelly 1:5:10 as per the site requirement	6.0		cu.m	
5	Providing and laying cement concrete of mix 1:2:4 a rough top ramp at the entrance, as required (average 5cm thickness)	10sq.m		sq.m	
6	Providing brick work in cement mortar 1:6 at front side (existing opened area)	1.60 cu.m		cu.m	
7	Supplying and laying of anti skid floor tiles (300mm x 300 mm) on the raised floor /kitchen platform as required	45.0sq.m		sq.m	

..... 2/-

8	Supplying and erection of sunshadet at front side , to the entire length of the new structure with coloured 0.47mm thickness metal sheet including necessary MS angles, runners,screws painting etc,	10.0sq.m	sq.m		
9	Providing and fixing wooden door of size 900mm X 1200mm with wooden frame of size 100mm x70mm and flush door shutters of thickness 35mm including all accessories / locking arrangement	2 Nos.	no		
10	Providing and fixing wooden windows with frame size 100mm x70mm and glazed shutters of thickness 30m including all accessories / locking arrangement				
	a) 900mmx 1200mm	1 nos	each		
	b) 1200mm x1200mm	1no.	each		
11	plastering of brick work in cement mortar 1:5 for nwely constructed brickwork	35 sq.m	sq.m		

NAME OF WORK ADDITION AND ALTERATION WORKS TO BE CARRIED OUT IN EXISTING DEPARTMENTAL CANTEEN ,ANNEX BUILDING, GST BHAVAN, NUNGAMBAKKAM,  
CHENNAI

KITCHEN					
Sl.No.	Description of work	Qty.	Rate	Unit	Amount
1	Dismantling of existing kitchen platform top and disposal the rubbish complete etc.,	6.56 Sq.m		Sq.m	
2	Dismantling of existing damaged wash area, including the brick work platform complete etc.,	0.12 Cu.m		Sq.m	
3	Dismantling and disposal of existing tiled floor in kitchen entire area complete as required	120 Sq.m		Sq.m	
4	Dismantling and disposing of existing grinder area platform upto a height of 15 cm and making good the same with necessary plastering etc.,	0.25cu.m		cu.m	
5	Construction of a new retaining wall of 15cm high at boundary of washing area including making good the washing area surface with water locking arrangement	0.12cu.m		Sq.m	
6	Providing and laying fire clay brick work at kitchen platform-1	1.75cu.m		cu.m	
7	Supplying and laying of new anti skid tiles (300mm x 300 mm) in entire kitchen area	127 Sq.m		Sq.m	
8	construction of new cupboard adjasant to the old cupboard with brick structure complete with smooth plastering etc.,	3.78 Sq.m		Sq.m	
9	Pastering of cupboard walls with cement mortar 1:6	20sq.m		sq.m	
10	Providing and fixing cuddapah stone shelves on new cupboard	5.0sq.m		sq.m	

DINING HALL					
Sl.No.	Description of work	Qty.	Rate	Unit	Amount
1	Dismantling of existing wall tiles all the sides of dining area and disposal the rubbish complete as required	80.0sq.m		Sq.m	
2	Dismantling of existing corroded MS window near the coffee shop and handing over the same to Department	5.4 Sq.m		Sq.m	
3	Supplying and laying of new pleasant looked good quality wall tiles of size 300mm x 450mm matching with the existing flooring	80.0sq.m		Sq.m	
4	Supplying and fixing of new powder coated aluminum window in dining hall (near coffee shop)	5.4 Sq.m		Sq.m	
5	Closing of existing window grill near sale counter with 6mm thick MS sheet	1 Sq.m		Sq.m	

NAME OF WORK : PAINTING OF EXISTING DEPARTMENTAL CANTEEN & RENOVATED GARAGE ,ANNEX BUILDING, GST BHAVAN, NUNGAMBAKKAM, CHENNAI

Sl.no	Description of work	Qty.	Rate	Unit	Amount
1	painting- smooth finish with one coat of primer + 2 coating of enamalon with good quality all sides in <b>KITCHEN</b>	350 Sq.m		Sq.m	
2	painting the wall smooth finish with one coat of primer + 2 coating of with enamal good quality all sides in <b>DINING HALL</b>	350sq.m		Sq.m	
3	scraping of existing white wash wall in proposed entire canteen area <b>(EXISTING GARAGE)</b>	200 sq.m		sq.m	
4	painting with emulsion smooth finish with one coat of primer + 2 coating of emulsion paint with good quality all sides in proposed entire canteen area <b>(EXISTING GARAGE)</b>	200sq.m		sq.m	

Sl.no	NAME OF WORK : PROVIDING ELECTRICAL INSTALLATION WORKS IN THE RENOVATED GARAGE AT ANNEX BUILDING, GST BHAVAN, NUNGAMBAKKAM, CHENNAI-34.	Description of work	Qty.	Rate	Unit	Amount
1		Wiring for light/ fan points , ex.fan points with insulated copper conductor of size in FRLS PVC conduit ( surface laying) as required	15		point	
2		Supplying and fixing GI switch board on surface, with modular plate in front, including 5/6 A modular sockets,switches etc. as per site requirements.	3 nos.		no.	
3		Supplying and fixing 6 pin 15/16A modular socket and switch with suitable size GI box, modular plate in front, etc. as per site requirements.	5nos		no.	
4		Wiring for circuit /sub main wiring along with earth wire with insulated copper conductor of size in FRLS PVC conduit ( surface laying) as required	85 meters		meter	
5		Supplying and Installaion of Ceiling fan with down rod of standard length,modular regulators etc., as required	4nos.		no.	
6		Supplying and fixing 450 mm heavy duty Industrial type exhaust fan in the existing hole with frame and other accessories etc., as required	1no		no.	
7		Supplying and fixing prewired fluorescent fittings including tube, ballast and all accessories etc., as required				
		a) 2 x 36 w	6nos.		no.	
		b) 1x36W	3nos.		no.	
8		Supplying and fixing 20A SPN Industrial socket on surface with 32A SP MCB,Metal enclosed plug including enclosures as per site requirements.	1no		no.	
9		Supplying and fixing one no 8way SPN SS MCB distribution board 240v on surface complete with all accessories but with out any circuit breaker / isolator etc., as required	1no		no.	
10		Supplying and fixing single pole 5A to 32A rating 240 /415 V miniature Circuit break in the existing MCB DB as required	8nos		no.	
11		Supplying and fixing 63A TP&N disconnecter fuse unit on the existing panel board with necessary fuse, making connections as required.	1no		no.	